



भा.कृ.अनु.प.- राष्ट्रीय लीची अनुसंधान केन्द्र

ICAR-NATIONAL RESEARCH CENTRE ON LITCHI
An ISO 9001:2008 Certified

(भारतीय कृषि अनुसंधान परिषद, कृषि मंत्रालय)

(Indian Council of Agricultural Research, Ministry of Agriculture)

मुशाहरी प्रक्षेत्र, मुशाहरी, मुजफ्फरपुर-842002 (बिहार) भारत

Mushahari Farm, Mushahari, Muzaffarpur - 842005 (Bihar) India

फोन Ph: 0621-2289475, 2281160

Email: nrclitchi@yahoo.co.in

फैक्स Fax: 0621-2281162

File No.14-1(22)/Estate/2018-19/Const. of Hut in Director Res. Campus/ 4217-4227 Dated: 21.02.2019
Speed/Registered Post

To,

(As per enclosed List)

Sub: Quotation for "Construction of Hut of Director Residential Compound" at ICAR-National Research Centre on Litchi, Muzaffarpur (Bihar) -reg.

Sir,

ICAR-National Research Centre on Litchi, Muzaffarpur (Bihar) is a unit of Indian Council of Agriculture Research, Ministry of Agriculture, Govt. of India, invites quotations for "Construction of Hut of Director Residential Compound" at this Centre from the reputed and experienced contractor.

Sl. No.	Particulars	Rate
1	" <u>Construction of Hut of Director Residential Compound</u> " (Specification attached)	

Accordingly it is requested to quote your rates after visiting the site and keeping in view of the following terms and conditions:-

1. The offered rates quoted for F.O.R. ICAR-NRC on Litchi, Mushahari Farm, Muzaffarpur basis should reach this office on or before 10.03.2019 up to 4.00 PM at the latest. The quotation received thereafter will not be entertained.
2. A valid proof of experience for doing this types of repairing works in other Govt./ICAR Institutes must be enclosed for consideration of quotation.
3. The terms and conditions and specification may be seen on institute website: [www:nrclitchi.org](http://www.nrclitchi.org) as well as CPP portal URL:<http://eprocure.gov.in/eprocure/app>.
4. Security Deposit @ 5% of quoted rate will be deducted from the bill which will be refundable after successfully completion of 01 year.

5. No advance payment will be made but payment is assured within 30 days from the date completion of ordered work/supply with satisfaction and installation.
6. The quotation of quantity of work of the indentor might be increased or decreased at the discretion of the ICAR-Director, ICAR-National Research Centre on Litchi, Muzaffarpur, while placing the supply order.
7. The rates should be quoted for F.O.R. ICAR-National Research Centre on Litchi, Mushahari Farm, Muzaffarpur basis.
8. Tendering firms will be required to indicate their valid income Tax, works registration No. and Sales Tax number and submit their authorization of the manufacturer.
9. Conditional offers are liable to be rejected summarily.
10. **Note lowest offer should not be mandatory to accept on part of this institute.**
11. The Director, ICAR-National Research Centre for Litchi, Muzaffarpur (Bihar) reserves the right to accept or reject any of the quotations without assigning any reasons thereof.

The quotations should be addressed to the Director, ICAR-National Research Centre for Litchi, (Indian Council of Agricultural Research) Mushahari Farm, Mushahari, Muzaffarpur – 842002 (Bihar) in a sealed cover supercribes “Construction of Hut of Director Residential Compound”

Yours faithfully,


Administrative Officer
ICAR-NRC on Litchi, Muzaffarpur
nrlitchi@yahoo.co.in

o/c
Dⁿ
21/2/19

Estimate of cost for construction of
Hand of Dr. Water Bungalow in N.R. of Musaffapur -

10.11.11

- ① Making 25 cm (10") dia bore up to 1.5m below ground level -
 $6 \times 1.50 = 9.00 \text{ m}^3$
- ② 63 cm Under Beam making of -
 6 No
- ③ Providing R.C. (1:1½:3) in Pillar Foundations
 Pillar - $6 \times 0.2 \times 0.30 \times \frac{0.63 \times 0.63}{4} = 0.56$
 $6 \times 0.2 \times \frac{0.25 \times 0.25}{4} \times 1.50 = 0.44$
 $\frac{0.56}{1.00} = 1.00 \text{ m}^3$
- ④ Providing R.C. (1:1½:3) in beam at ground level
 $10 \times 0.25 \times 0.30 = 0.75 \text{ m}^3$
- ⑤ Providing 100# M.S. (1:4)
 $10 \times 0.25 \times 0.45 = 1.12 \text{ m}^3$
- ⑥ Providing R.C. (1:1½:3) in Raft slab -
 $11 \times 4 \times 0.10 = 4.40 \text{ m}^3$
- ⑦ Providing R.C. (1:1½:3) in Pillar -
 $6 \times 0.2 \times \frac{0.25 \times 0.25}{4} \times 2.20 = 0.65 \text{ m}^3$
- ⑧ Providing M.S. Rod in R.C. work -
 $1.00 + 0.75 + 4.40 + 0.65 = 6.80 \text{ m}^3$
 $38 \text{ kg per m}^3 = 398.40 \text{ kg}$

ole Adcu. dmk
 Du
 21/2/19

(9) Providing P.C.C (1:1.5:3) in Jambaloon
 $3.30 \times 3.30 \times 0.10 = 1.09 \text{ m}^3$

(10) Providing 12mm steel C/P (1:4)

10 x 0.4	= 4.20 m ²
4 x 6 x 0.25 x 2.20	= 13.20 m ²
2 x 10 x 4	= 80.00 m ²
	<hr/>
	97.40